

## 800 pax room

**ESC 2020**

On-site construction	22 August 2020 until	03 September 2020
Operational	29 August 2020 until	02 September 2020

### System Setup

Room measurements 26 x 41 meter

### Room Setting

2	Entrance gate	
4	Table outside entrance	
2	Chair table with modesty board	
5	Chair	
1	Lectern grey	
1	Table	60x60 cm next to lectern

### Video Facilities

2	Video/data projector 12,000 ansi lumen HD, 3DLP	
2	Front/rear proj. screen 780x440	
1	Camera HD Pan AW-HE130KE (incl Remote)	
1	LED screen 46"	DSM
1	LED screen 65"	Overflow screen
1	Infrastructure	

### Lighting Facilities

20	LED Spot 49deg. 3000k	
4	Profile LED zoom 20-36deg. 2700-6000k	Spotlight on lectern
6	LED Fresnel 2700-6000k	Spotlight on faculty table
13	LED Par RGBW AUV CLF Hercules	

### Crew, Labour and affiliated costs

2	Condensor Microphone	Lectern microphone
4	Condensor Microphone	Faculty table microphone
4	Dynamic Microphone	Q&A microphone
1	Digital audiomixer 32-channel	
1	Column Array Meyer CAL 64	
1	DI for external audio source	
3	Loudspeaker active	Monitoring for stage and tech use

### Crew, Labour and affiliated costs

